ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Notification dated 27th November 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on the 11th December 1939, for constructing the Kannada Primary School at Hoskote.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Bangalore Division, should be addressed to the Executive Engineer, Bangalore Division, in a sealed cover and superscribed as "Tender for constructing the Kannada Primary School at Hoskote." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate challan for having credited into the treasury the deposit amount of Rs. 280, two hundred and eighty only under 17(*a*) P. W. Deposits in Mysore Government Bonds, duly endorsed at a face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 11th December 1939 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Bangalore Division, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 3 each.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates those given will hold good for any quantity, whether higher or lower than in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of April 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 1-14-0 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Approximate quantities for constructing the Kannada Primary School at Hosko.

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
			Rs. a. p.		Rs. a. p.	Rs.
1	Earthwork excavation for foundation and filling in basement with watering and tamping, etc.	C.yd.	0 3 6	92		
2	Burnt stone jelly concrete in lime mortar 1 : 2 : 4	C.ft.	0 3 9	882		
3	Burnt size stone in mud with bond stones at every 6 feet in each layer, etc.	C.ft.	0 3 6	1,905		
4	Burnt brick in mud with bond stones wherever necessary	,,	0 3 0	2,247		
5	Burnt brick in mortar	,,	0 4 0	630		
6	Burnt size stone in mortar for pillars, with bond slabs, for every 4 feet in height, exposed faces one line dressed, etc., complete	,,	0 8 0	91		
7	Burnt stone slabs 6" thick, one line dressed and fixed in mortar	,,	0 5 0	508		
8	Burnt stone slab pillars, with two lines dressing, including cutting grooves, at top, etc.	S.ft.	0 6 0	366		
9	Teakwood wrought and put up including two coats of wood oiling, etc.	C.ft.	4 8 0	245·79		
10	Roofing with Madras terrace with a camber of 1 in 40 bottom course laid with terrace brick in mortar, on edge, at the top 3" kappee with three courses of flat tiles, and bottom and top plastered smoothly	Sqr.	28 0 0	15·39		

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Word
			Rs. a. p.		Rs. a. p.	R
11	Teakwood doors with frames $4\frac{1}{2}'' \times 3\frac{1}{2}''$ in section, panelled shutters $1\frac{1}{4}''$ thick with iron clamps, iron fittings, etc., complete including two coats of green paint of Lac Factory	Sqr.	1 8 0	98		
12	Teakwood windows with frames $3\frac{1}{2}'' \times 4''$ in section panelled shutters $1\frac{1}{4}''$ thick in four halves $\frac{3}{4}''$ dia. iron bars, iron clamps, and iron fittings, etc., complete including two coats of Lac, Factory green paint, etc.	S.ft.	1 10 0	240		
13	Providing and fixing R.C.C. perforated trellis work in front pannels over terrace in parapet	S.ft.	0 12 0	436		
14	Burnt brick in mortar block cornice including blocking course, chunam plastering, white washing, etc., complete	R.ft.	0 3 0	271		
15	Burnt brick in mortar parapet wall over the terrace, including cornice, chunam plastering, white wash, etc., complete	R.ft.	0 12 0	226		
16	Chunam plastering two coats $\frac{3}{4}''$ thick	Sqr.	2 12 0	68.99		
17	Rolled steel girders double for Bressummers with distance pieces, etc.	Cwt.	14 0 0	10.21		
18	Boxing girders with cement concrete and plastering, etc.	R.ft.	0 8 0	88		
19	Flooring with $1\frac{1}{2}''$ thick cement concrete over 3" thick burnt stone jelly concrete in chunam and plasterng with cement $\frac{1}{2}''$ thick mixed with red ochre and cut into squares and smoothness	Sqr.	20 0 0	13.20		
20	White washing, two coats	"	0 3 9	69.00		
21	Cement pointing to basement	"	3 0 0	8.76		
22	Zinc water spouts	R.ft	0 6 0	36		
23	Old S. M. Rail including hoisting, and fixing, etc.	R.ft.	1 0 0	336		
24	R.C.C. tree guards	Each	2 12 0	5		
25	Teakwood gate shutters with clamps, iron fittings, etc., complete	S.ft.	1 0 0	2		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

PRIVATE ADVERTISEMENT.

MYSORE GOVERNMENT LIFE INSURANCE DEPARTMENT, (PUBLIC BRANCH).

Application having been received for the issue of a duplicate of Policy No. 30598/C27766 on the life of Mr. Lingaiah, Police Constable, No. 326, Traffic Branch, Kalasipalyam Police Station, Bangalore City, it is hereby notified that the duplicate will be issued unless valid objection therefor is received by the undersigned within one month from this date.

BANGALORE,
Dated 29th November 1939.

M. VIRARAJA URS,
Secretary.

Printed by the Superintendent at the Government Press, Bangalore, 1939.